



2020 Street Improvements West Area (Contract 20-102)



CONSTRUCTION BULLETIN

Construction Schedule

- See the project phasing and schedule map on the back of this bulletin
- Visit burnsvillemn.gov/roadwork for updates during construction

Project Updates

Visit burnsvillemn.gov/roadwork and click the “subscribe” button to sign up for weekly email and text message updates during construction.



Subscribe

Notify Us

Visit burnsvillemn.gov/roadwork and click the “notify us” button to let us know about:

- Irrigation or invisible fence you have within 5' of the curb, driveway, or sidewalk
- Landscaping you have within 5' of the curb, driveway, or sidewalk
- Questions you have about trees in the boulevard
- Special events you have planned for the summer. The City and contractor will work to accommodate these
- Disabilities or medical needs. The City and contractor will work to accommodate these



Notify Us

Construction Safety

- Stay away from equipment, materials, and trenches whenever possible
- Access to your property will be maintained to the extent feasible during construction
- Preserve survey stakes and utility flags during construction
- Observe posted warning and no parking signs

Road Surface and Dust

- Streets will be rough when pavement is removed or milled
- Where pavement is removed, the contractor will water the surface to minimize dust. Drive slow to minimize dust
- The contractor will sweep adjacent roads periodically to minimize mud tracking

Disturbed Boulevards

- Boulevards will be disturbed adjacent to driveways, curbs, sidewalks, and fire hydrants being replaced
- Disturbance is typically 3'-5' adjacent to curbs, driveways, and sidewalks and 5'-10' around hydrants
- Disturbed turf areas will be restored with topsoil and seed
- The contractor is responsible for maintaining seed for 45 days until it becomes established after which the adjacent property owner is responsible for maintenance
- New seed requires frequent watering
- Do not mow seeded areas until the grass is nearly tall enough to fall over and when mowing use the highest setting till next season

Driveways and Curb

- Curbs and adjacent driveways will be replaced where significantly damaged or settled
- Driveway sections will be restored with the same material as existing
- Concrete curb and driveways take 5-7 days to cure. Please refrain from driving on them during that time

Primary Inspector

Nils Hudyma
City of Burnsville
612-619-5892
nils.hudyma@burnsvillemn.gov

Secondary Inspector

Cody Pietz
City of Burnsville
952-356-6839
cody.pietz@burnsvillemn.gov

Project Engineer

John Schmeling
City of Burnsville
952-895-4457
john.schmeling@burnsvillemn.gov

Contractor

Dan Dhaene
Northwest
952-292-8455

Please contact the primary inspector above with any questions or concerns during construction.

Thank you for your
patience during this
inconvenience!



Engineering Department

100 Civic Center Parkway | Burnsville, MN 55337
952-895-4534 | construction@burnsvillemn.gov

2020 Street Improvement West Area (Contract 20-102)

Phase and Schedule*

- █ Phase 1: April 20 - May 22
- █ Phase 2: April 27 - May 22
- █ Phase 3: May 4 - June 12
- █ Phase 4: May 11 - June 26
- █ Phase 5: June 8 - August 14

*Start and end dates subject to change.
 Visit www.burnsvillemn.gov/roadwork
 for schedule updates.

